



Shoreline Management Planning

Prepared by:

Department of Public Works

June 14, 2016

2011 Nourishment

- Occurred between May 24, 2011 and October 27, 2011
- The largest locally funded beach nourishment accomplished to date in the United States.
- 4.6 million cubic yards along 10 miles of oceanfront
- Project construction cost \$30.8 million
- Five years of environmental permitting
- Project planning, design, permitting, construction & monitoring handled by Coastal Science & Engineering (CSE)
- Project segmented into 4 reaches



Beach Maintenance Plan

- Developed per FEMA regulations 44CFR 206.226 (j)
- Qualify for FEMA Public assistance for sand losses arising from a significant storm event
- Annual post-nourishment monitoring condition surveys
- Triggers for Renourishment
 - Renourish beach at 6 years
 - OR
 - Greater than 50% loss of sand placed in the system (whichever comes first)



Planning

- Per statutory guidelines the Town could not extend the contract of CSE
- Developed a Request for Qualifications
- Three Statement of Qualifications were submitted
 - Coastal Science & Engineering (CSE)
 - Coastal Planning & Engineering/CB & I
 - Moffat & Nichol
- Evaluation Committee was formed
- Interviews conducted with each of the proposers
- Board of Commissioners approved review committee recommendation at May 4, 2016 for CSE to continue services



Project Goals

- Development of a long-term Shoreline Management Master Plan (30-years)
 - Measurable & Quantifiable Goals in Design
 - Improvement to existing program
 - Identification of sand sources
 - Permitting Efficiencies
 - Structured Dune Management Program
 - Focus on highly erosive areas
 - Investigate potential to coordinate with neighboring nourishment projects
- Initiation of a short term program
- Goal to renourish in Summer 2018



Project Schedule

- Parallel tracks for the short term and long-term permitting
- 2018 Re-nourishment track is the critical path
 - **June –Sept 2016** : Project Planning Phase
 - Define Project Goals and Objectives
 - Define beach dune system & target beach conditions
 - Develop re-nourishment requirements/dune stabilization alternatives
 - Conduct borrow area survey & obtain borings
 - **Oct-Dec 2016**
 - Design Analyses for fill scenarios & cost estimates
 - Pre-Application meeting(s) with resource & regulatory agencies
 - Supporting environmental documents
 - Conduct beach survey for “winter” condition
 - Analyze and update erosion rates



Project Schedule (con't)

- **Jan –Dec 2017** : Project Design/Permitting Phase
 - Coastal Engineering Analysis
 - Complete environmental reports
 - Conduct pre-application meetings with regulatory agencies
 - Submit permit applications
 - Conduct beach survey(s)
 - Finalize Design and specifications
 - Receive Permits
- **Jan-Feb 2018**: Bidding Phase
 - Request Bids & Receive Bids
 - Select Contractor
- **May-Aug 2018**: Construction Phase
 - Construction
- **Sept-Dec 2018**: Post-Construction Survey/Final Report



Long-Term Plan (30-yr)

- Determine Scale/Protection Level
 - (Minimum-Optimal-Maximum)
- Evaluate nourishment volumes/costs
 - Relate to project scales
 - Analysis of fill section volume vs. cost
- Outline borrow requirements
 - Identify potential future borrow sites
- Model Simulations
 - Erosion scenarios and vulnerable properties
- Permitting Requirements
 - Developing a programmatic document to reduce permitting times
- Maintenance and Monitoring Requirements
 - Refine Re-nourishment triggers
- Final Report

