



NOTES:

1. Concrete Dumpster Pad shall be a minimum 6" thick 3,000 psi concrete with a min. W1.4xW1.4 welded wire fabric. Dumpster aprons subject to Sanitation vehicle loads shall be a minimum of 8" thick with #4 steel reinforcement spaced @ 12" o.c.
2. Special conditions may warrant exceptions to this detail. Subject to approval by Town Engineer or PW Director.
3. All wood members shall be pressure treated.
4. 4"x4" posts a No.2 grade or better.
5. All nails and connectors shall be hot dipped galvanized or in accordance with NC Building Code, current edition.
6. Wood posts embedment depth and footing shall be designed and constructed in accordance with NC Building Code, current edition.
7. Alternative screening material may be considered on a case by case basis.
8. A minimum 16' vertical clearance shall be provided at the dumpster pad.
9. Multiple bulk container layouts shall be reviewed & approved by the PW Director.



TOWN OF NAGS HEAD
 DEPARTMENT OF PUBLIC WORKS
 P.O. BOX 99
 NAGS HEAD, NC 27959
 252.441.1122 • www.nagsheadnc.gov

**TYPICAL COMMERCIAL DUMPSTER PAD
 WITH WOOD SCREEN DETAIL**

(FOR SIDE LOADING DUMPSTER CONFIGURATIONS)

SCALE: NONE
 ISSUE DATE: 7-9-2015
 REVISION DATE:
 SHEET NO: 1 OF 1
 DRAWN BY: DMR

DETAIL NO.:
203