

TOWN OF NAGS HEAD FY 18/19
PROJECT CONSTRUCTION UPDATE
April 24, 2019



The following is intended to provide Town of Nags Head residents with a description, schedule and location of proposed construction projects and the potential conditions that may accompany construction activities. The following conditions can be expected in the area of construction work:

- Vehicle and pedestrian access may be restricted.
- Customers may be without water for a short duration while work is in progress. Property owners will be notified in advance of any planned service disruptions.
- Town services will continue uninterrupted.
- *Work will typically be conducted from 7:30 am to 5:00 pm.*

PROJECT AREA #2
(NAGS HEAD ACRES/VISTA COLONY SUBDIVISIONS)

WORK DESCRIPTION

Installation of (7) individual groundwater lowering wells with connecting force main, and appurtenances. Construction activities will include open cut trench work, horizontal directional drilling, underground forcemain pipe installation, well construction and incidental work.

WORK PROGRESS

Week of April 22, 2019—Selective vegetative clearing will be conducted along portions of the construction area. Underground force main installation will commence via horizontal directional drilling along the eastern extents of the project limits and then relocate to the southwestern portion of W. Bridge Lane. Work will also be conducted in the vicinity of Well-field Rd. with pipe installation occurring from the discharge point eastward back into the Nags Head Acres subdivision.

PROJECT SCHEDULE—

BEGIN: Late April 2019

COMPLETE: Early June 2019

EXPECTED WORK CONDITIONS*

Single lane road closures, temporary pedestrian closure and detour, groundwater lowering pump operation, heavy machinery operation, increased truck traffic, ground restoration, and other incidental work. A well point system with trailer mounted pump operation will occur in areas specified for open trench cut. During certain periods of construction, pump operation may continue overnight. If you have irrigation lines, sprinkler heads or landscaping that is located within the right-of-way, please mark with paint, flagging or other markings so that the contractor can easily identify in advance of excavation.

CONTACT
INFORMATION

Contractor | Hatchell Concrete Inc. | 252.473.6074 | hatchell_concrete@earthlink.net

Town of Nags Head | David Ryan, P.E. | 252.441.6221 | david.ryan@nagsheadnc.gov

